



American Concrete Institute

Use of Heavy Equipment on Existing Bridges During Construction

Kyle Eyre, P.E., P.Eng, *Kiewit Engineering Group Inc.*



American Concrete Institute



Kiewit

Always advancing

Agenda

- About Kiewit
- Risk Mitigation
- Design Criteria
- Loading
- Methods
- Design Best Practices



American Concrete Institute



Kiewit

Always advancing

ABOUT KIEWIT

- The Kiewit Difference

People

Integrity

Excellence

Stewardship



American Concrete Institute



Kiewit

Always advancing

RISK MITIGATION



American Concrete Institute



Kiewit

Always advancing

RISK MITIGATION

- We Have Risk and we must take risk mitigation measures to keep the public and workers safe

“It is the Company’s policy to properly and systematically address the design and construction of temporary structures and other construction devices used in our operations. When the design is not provided by the owner, the liability assumed by the Company requires even greater attention to minimize the risk of failure. The design and construction of temporary structures and other construction devices requires thoughtful risk analysis and risk mitigation measures that begin with appropriate selection of designers, an independent review of the resultant design, and proper inspection during construction.

Districts are to follow the Design and Construction of Temporary Structures and Construction Devices Manual.”



American Concrete Institute



Kiewit

Always advancing

RISK MITIGATION

- TSCD

Temporary Structures and Construction Devices – elements that are designed, developed, and constructed for the sole purpose of aiding in the construction of permanent works.



American Concrete Institute




Kiewit

Always advancing

RISK MITIGATION

- CONCEPTUALIZE
- DESIGN
- DESIGN REVIEW
INSPECT and VERIFY



American Concrete Institute



Kiewit

Always advancing

RISK MITIGATION



RISK MITIGATION

KIEWIT CORPORATION

TEMPORARY STRUCTURES AND CONSTRUCTION DEVICES MANUAL | REV 10.0

TABLE 3.18: PERMANENT STRUCTURES – TEMPORARY CONDITION DURING CONSTRUCTION / ERECTION

Risk Level	Attributes	Designer	Design Reviewer	Inspector(s)
Low (See Note 1)	<ul style="list-style-type: none"> ✓ Stresses and loading during construction of permanent works may impact structure differently from final loading conditions. ✓ Overhang brackets on deck pours need to have anchorages and overturning forces on girders reviewed. 	Project Personnel to confirm with client that temporary conditions will not adversely affect structure Documentation required	Not required	No review of design process required in field. Erection checking covered elsewhere.
Moderate	<ul style="list-style-type: none"> ✓ Structures where stability of individual members during construction needs to be reviewed, but overall structure stability is not at risk. ✓ Handling of long pre-cast or steel plate girders. Stability and external bracing require Design and Design Review. ✓ Erection of structural steel buildings, frames before final bracing is installed. 	KIE	Not required	Experienced District Personnel to review construction designs for completeness and constructability
		District PE OR Consultant A	KIE OR Consultant B	
High	<ul style="list-style-type: none"> ✓ Any structure that is unstable in a global manner until final erection is complete. ✓ Steel truss cantilever bridge erection ✓ Segmental pre-cast and CIP bridge structures ✓ Box girder bridges requiring cast in place deck for stability ✓ Long-span bridge girders or trusses ✓ Exposure to public in partially erected condition 	Erection procedures designed by KIE	Consultant	Experienced District Personnel to review construction designs for completeness and constructability
		Erection procedures designed by Consultant A	KIE OR Consultant B	



American Concrete Institute







Kiewit

Always advancing

DESIGN CRITERIA

- ASCE 37-14
- ACI 318
- AASHTO LRFD Bridge Construction Spec.
- AASHTO Guide Design Spec. for Bridge Temp. Works
- Others: AREMA, Kiewit CEDC



LOADING

- DEAD LOADS
 - Structure Self Wt.
 - Wearing Surface
 - Barriers
 - Utilities



AASHTO 3.4.2.1: $DC = 1.25$

Evaluation of Strength III for max. force effect during construction



American Concrete Institute



Kiewit

Always advancing

LOADING

- LIVE LOADS
Equipment Self Wt.
Dynamic Impact



AASHTO 3.4.2.1: $LL = 1.50$, $IM = 1.33$

Evaluation of Strength III for max. force effect
during construction



American Concrete Institute



Kiewit

Always advancing

LOADING

- EQUIPMENT
 - Excavators on Superstructure (If necessary)
 - Haul Trucks
 - Ground Based Excavators
 - Ground Based Cranes



LOADING



- EQUIPMENT

- Excavators ~ 40 to 100+ kip (Larger yields more economical operation)
- Compare to AASHTO Truck 72 kip (Greater need for engineering)
- Consider both uniform track and concentrated point loading

METHODS

- DECK REMOVAL
 - CORE HOLES (INITIAL)
 - DECK SLOTTING (LEAVE ENOUGH FOR GIRDER STABILITY)
 - HYDRAULIC HAMMER ATTACHMENTS
 - DIAMOND BLADE SAWS (LIMITED)
 - DIAMOND WIRE SAWS (PREFERRED)



METHODS



American Concrete Institute



Kiewit

Always advancing

METHODS



American Concrete Institute



Kiewit

Always advancing

METHODS



American Concrete Institute




Kiewit


Always advancing

METHODS

- STAGE SEQUENCES
 - EVALUATE EVERY STEP
 - REDUCED WIND EXPOSURE
 - EXAMPLE SHOWING A TYPICAL STAGE DEMO




METHODS




METHODS

Stage 1 – remove
outer bike lane rail –
Saw cut in ~10'
pieces – pick with
Excavator through
existing railing holes
and load directly into
truck




METHODS

Stage 2 – remove
outer bike lane deck –
Saw cut into ~10' long
pieces – pick with
excavator and load
directly into truck




METHODS

Stage 3 – remove
inner Barrier Rail –
Hoe ram excavator
demo




METHODS

Stage 4 – remove
Inner bike lane deck –
saw cut into ~10 long
pieces and pick with
excavator and slab
grab – load directly
into truck




METHODS

Stage 5 – Use excavator W/ Shear to remove existing Girders and Stringers. Girders picked Full length (~42') with crane from Trestle




METHODS

Stage 6 – Wire Saw
Existing Bent and top
of concrete piles -
pick with Crane from
Trestle



METHODS

Stage 7 – Shear Existing Piles (16” Conc.) with 345 excavator sitting on existing bridge. Piles picked with Crane from Work Trestle



METHODS



American Concrete Institute



Kiewit

Always advancing

METHODS



American Concrete Institute



Kiewit

Always advancing

DESIGN BEST PRACTICES

- ADD SUPPLEMENTAL SUPPORT WHEN NECESSARY



American Concrete Institute




Kiewit

Always advancing

DESIGN BEST PRACTICES

- EVALUATING EA STAGE EFFICIENTLY
 - HAND CALCS
 - RISA 3D
 - MIDAS CIVIL



American Concrete Institute



Kiewit

Always advancing

DESIGN BEST PRACTICES

- CONSIDER RISKS
 - HIGH RISK SAFETY
 - HIGH RISK COST
 - ADJACENT STRUCTURES
 - PLAN THE WORK , WORK THE PLAN



American Concrete Institute



Kiewit

Always advancing

DESIGN BEST PRACTICES

- DESIGN TIPS
 - CONSERVATIVE LOAD FACTORS
 - CONSIDER SERVICEABILITY (IF APPLICABLE)
 - TYPICAL EXCAVATOR 80 KIP

DESIGN BEST PRACTICES

- DESIGN TIPS
 - CRANE MATS (IF NECESSARY)
 - LOAD DISTRIBUTION FRAMES (BYPASS DECK)
 - PROVIDE TEMP. FALSEWORK SHORING (IF NECESSARY)

QUESTIONS?



American Concrete Institute



Kiewit

Always advancing

Thank you

For the most up-to-date information please
visit the American Concrete Institute at:
www.concrete.org



American Concrete Institute



Kiewit

Always advancing